

Your P.O. #: BN501012
Your Project #: SACRED HEART
Site:500012507
Your C.O.C. #: n/a

Attention: Roland Lawton
Dufferin-Peel Catholic District School Board
40 Matheson Blvd
Mississauga, ON
CANADA L5R 1C5

Report Date: 2009/07/10

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: A983148
Received: 2009/07/06, 11:36

Sample Matrix: Water
Samples Received: 2

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Method Reference
Metals Analysis by ICPMS (as received) ¶	2	2009/07/08	2009/07/09	CAM SOP-00447	EPA 6020

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) Metals analysis was performed on the sample 'as received'.

Encryption Key

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

JAMES ASPIN, Project Manager
Email: James.Aspin@maxxamAnalytics.com
Phone# (905) 817-5700 Ext:5771

=====
Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. SCC and CALA have approved this reporting process and electronic report format.

For Service Group specific validation please refer to the Validation Signature Page

Total cover pages: 1

Maxxam Job #: A983148
 Report Date: 2009/07/10

Dufferin-Peel Catholic District School Board
 Client Project #: SACRED HEART
 Project name: 500012507
 Your P.O. #: BN501012

ELEMENTS BY ATOMIC SPECTROSCOPY (WATER)

Maxxam ID			CZ3499	CZ3500		
Sampling Date			2009/07/03 06:00	2009/07/03 06:35		
COC Number			n/a	n/a		
	Units	Criteria	SACRED HEART STANDING	SACRED HEART FLUSHED	RDL	QC Batch

Metals						
Lead (Pb)	mg/L	0.01	0.0007	ND	0.0005	1871580

ND = Not detected
 N/A = Not Applicable
 RDL = Reportable Detection Limit
 QC Batch = Quality Control Batch
 Criteria: Ontario Regulation 243/07 made under the Safe Drinking Water Act, 2002.

Released June 7, 2007

Maxxam Job #: A983148
Report Date: 2009/07/10

Dufferin-Peel Catholic District School Board
Client Project #: SACRED HEART
Project name: 500012507
Your P.O. #: BN501012

Package 1	5.7°C
-----------	-------

Each temperature is the average of up to three cooler temperatures taken at receipt

GENERAL COMMENTS

Results relate only to the items tested.

Dufferin-Peel Catholic District School Board
 Attention: Roland Lawton
 Client Project #: SACRED HEART
 P.O. #: BN501012
 Project name: 500012507

Quality Assurance Report
 Maxxam Job Number: MA983148

QA/QC Batch	QC Type	Parameter	Date Analyzed yyyy/mm/dd	Value	Recovery	Units	QC Limits
1871580 JBW	MATRIX SPIKE	. Lead (Pb)	2009/07/09		102	%	80 - 120
	Spiked Blank	. Lead (Pb)	2009/07/09		98	%	90 - 110
	Method Blank	. Lead (Pb)	2009/07/09	ND, RDL=0.0005		mg/L	
	RPD	. Lead (Pb)	2009/07/09	NC		%	25

ND = Not detected
 NC = Non-calculable
 RPD = Relative Percent Difference
 SPIKE = Fortified sample

Notification Log

Maxxam Job #: A983148
Report Date: 2009/07/10

Dufferin-Peel Catholic District School Board
PROJECT #: SACRED HEART
Site: 500012507

No Reportable Regulation Exceedences Noted.

Validation Signature Page

Maxxam Job #: A983148

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).



BRAD NEWMAN, Scientific Specialist

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. SCC and CALA have approved this reporting process and electronic report format.