

Your Project #: ST.MARGARET OF SCOTLAND  
Site:500019514  
Your C.O.C. #: n/a

**Attention: Roland Lawton**

Dufferin-Peel Catholic District School Board  
40 Matheson Blvd  
Mississauga, ON  
CANADA L5R 1C5

**Report Date: 2009/06/25**

**CERTIFICATE OF ANALYSIS**

**MAXXAM JOB #: A974742**

**Received: 2009/06/18, 12:43**

Sample Matrix: Water  
# Samples Received: 2

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Method Reference
Metals Analysis by ICPMS (as received) 0	2	2009/06/24	2009/06/24	CAM SOP-00447	EPA 6020

\* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) Metals analysis was performed on the sample 'as received'.

**Encryption Key**

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

JAMES ASPIN, Project Manager  
Email: James.Aspin@maxxamAnalytics.com  
Phone# (905) 817-5700 Ext:5771

=====  
Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. SCC and CALA have approved this reporting process and electronic report format.

For Service Group specific validation please refer to the Validation Signature Page

Total cover pages: 1

Maxxam Job #: A974742  
 Report Date: 2009/06/25

Dufferin-Peel Catholic District School Board  
 Client Project #: ST.MARGARET OF SCOTLAND  
 Project name: 500019514

**ELEMENTS BY ATOMIC SPECTROSCOPY (WATER)**

Maxxam ID			CV2758	CV2759		
Sampling Date			2009/06/17 06:35	2009/06/17 07:12		
COC Number			n/a	n/a		
	<b>Units</b>	<b>Criteria</b>	<b>ST MARGARET OF SCOTLAND KITCHEN STAFFROOM(STANDING)</b>	<b>ST MARGARET OF SCOTLAND KITCHEN STAFFROOM(FLUSHED)</b>	<b>RDL</b>	<b>QC Batch</b>

<b>Metals</b>						
. Lead (Pb)	mg/L	<b>0.01</b>	0.0019	0.0008	0.0005	1857776

N/A = Not Applicable  
 RDL = Reportable Detection Limit  
 QC Batch = Quality Control Batch  
 Criteria: Ontario Regulation 243/07 made under the Safe Drinking Water Act, 2002.  
 Released June 7, 2007

Maxxam Job #: A974742  
Report Date: 2009/06/25

Dufferin-Peel Catholic District School Board  
Client Project #: ST.MARGARET OF SCOTLAND  
Project name: 500019514

Package 1	4.7°C
-----------	-------

Each temperature is the average of up to three cooler temperatures taken at receipt

**GENERAL COMMENTS**

**Results relate only to the items tested.**

Dufferin-Peel Catholic District School Board  
 Attention: Roland Lawton  
 Client Project #: ST.MARGARET OF SCOTLAND  
 P.O. #:  
 Project name: 500019514

Quality Assurance Report  
 Maxxam Job Number: MA974742

QA/QC Batch	QC Type	Parameter	Date Analyzed yyyy/mm/dd	Value	Recovery	Units	QC Limits
1857776 ADA	MATRIX SPIKE	. Lead (Pb)	2009/06/24		101	%	80 - 120
	Spiked Blank	. Lead (Pb)	2009/06/24		96	%	90 - 110
	Method Blank	. Lead (Pb)	2009/06/24	ND, RDL=0.0005		mg/L	
	RPD	. Lead (Pb)	2009/06/24	NC		%	25

ND = Not detected  
 NC = Non-calculable  
 RPD = Relative Percent Difference  
 SPIKE = Fortified sample

## **Notification Log**

Maxxam Job #: A974742  
Report Date: 2009/06/25

Dufferin-Peel Catholic District School Board  
PROJECT #: ST.MARGARET OF SCOTLAND  
Site: 500019514

No Reportable Regulation Exceedences Noted.

**Validation Signature Page**

**Maxxam Job #: A974742**

---

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

*Cristina Nervo*

---

CRISTINA NERVO, Scientific Services

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. SCC and CALA have approved this reporting process and electronic report format.